Sl. No.	Items of work	Unit	Transformer Building Room	Lean-to room of Old Stores	Hall adjoining the Trasformer work shop
12a	Earth work excavation for foundation and disposal of excess earth.	C.yd.	...	7·6	...
b	Stone masonry in clay foundation and basement including through stones fixed at 6'-0" intervals in every course.	C.ft.	..	204	...
c	Burnt brick in mortar superstructure ...	„	...	634	...
d	Stone slabs 6" thick roughly dressed and fixed in mortar.	S.ft.	...	160	20·00
13a	Doors: teak wood with panelled shutters and accessory fittings, complete as per existing ones.	„	...	56	...
b	Fixing expanded metal to outside of windows, as per existing work.	„	...	88	...
14a	Rolled steel work new wrought and fixed complete.	Cwts.	...	20	27·71
b	Do old steel work fixed complete.	„	...	7·3	...
c	Digging holes in walls and fixing bearing slabs, rafters, etc., in mortar.	Each	...	13	...
d	Roofing with old corrugated G. I. sheets with new Galvd. iron bolts and nuts and lead washers, etc., with overlap of 3 corrugation at sides and 1'-9" at ends. (sheets supplied departmentally).	Sqr.	..	12·80	...
e	Binding wall 9" x 9" on top of roofing built in brick in mortar with plaster, white wash, etc,, complete.	R.ft.	...	19	
f	6" plain cornice brick in mortar with plaster complete.	„	...	19	...
g	Chunam borders 6" x 6" built it brick in mortar with plaster, etc., complete.	„	...	19	
h	Removing the existing top roof to fecilitate fixing bottom roof and re-doing the same after the latter is fixed.	„	...	1 Item	...
15	Chunam plastering 2 coats ..	Sqr.	...	14·25	2·00
16	Supporting roof for dismantling walls. ...	...	...	...	1 Item
17	Dismantling masonry and removing the debris to a distant place.	C.ft.	...	...	271
18	Old bricks in new mortar ...	„	...	...	93
19	Petty repairs including fixing of gutters, fixing trusses to I-Beams, with necessary plates and rivets and repairing leaks of roof.	„	...	...	1 Item

V. R. COWSIK,
For *Chief Electrical Engineer.*

MYSORE DEPARTMENT OF HEALTH.

BUREAU OF LABORATORIES.

VACCINE INSTITUTE.

Abstract Notification, dated 16th October 1933.

Sealed tenders for the supply of certain articles required for twelve months from 1st January 1934 to 31st December 1934 (both days inclusive) will be received by the Superintendent, Vaccine Institute, Bangalore, at his office upto 11 A.M. on Friday, the 15th December 1933.

For details, please see the *Mysore Gazette*, dated 12th October 1933, Part VI, pages 1269 to 1274.